

Erection and dismantling procedures for Mobile or Tower

Scaffold specifications for 0.700m wide Ali-Scaff

- ALI SCAFF is a "Light Duty" scaffold with a Uniformly Distributed Load (UDL) of 225kg's and MUST NOT be exceeded.
- All 0.7m wide scaffolds are intended for low level light duty use only or erected in such a way as to give them stability i.e. in an alleyway between 2 buildings with no chance of toppling.
- ALL scaffolds MUST NOT BE HIGHER THAN 5 METRES from the ground or supporting structure to the TOPMOST GUARDRAIL of the working platform.
- The height of the top working platform must be no more than <u>TWO</u> times the minimum base dimension of the structure for scaffolds UNDER 1.8 METRES in height.
- The height of the top working platform must be no more than <u>THREE</u> times the minimum base dimension of the structure for scaffolds OVER 1.8 METRES in height.
- ALL SCAFFOLDS EXCEEDING 5 METRES TO THE TOPMOST GUARDRAIL OF THE WORKING PLATFORM
 MUST BE ERECTED, ALTERED AND MAINTAINED BY PERSON HOLDING A CERTIFICATE OF
 COMPETENCE IN SCAFFOLDING.
- The manufacturer recommends that scaffold erectors & users adopt the use of installing an Outrigger
 at each corner for low level scaffolds to maintain stability when basing out the scaffold. The
 recommended placement of Outriggers are displayed in this procedure.
- There must be a hatch platform within 3 metres of ground level to prevent deforming of the scaffold.
- If not using Guardrail Frames and using an End Frame instead place three yellow ledgers on three transom levels to achieve minimum legal guardrail requirements.
- Erectors MUST use hatch decks on 0.700m wide for safe access within the scaffold structure and NOT climb the outside of the scaffold to gain access to the working platform.
- Ladders should protrude through the Access Deck hatch as depicted in the pictures.
- Never use damaged equipment. Either repair immediately, delete from service or scrap.
- Scaffolds MUST have guardrails, midrails and toeboards on ALL working platforms.
- Ensure that the Mobile or Tower is suitable for its intended use.
- Ensure that the mobile is re-levelled when moved to a new position.
- Mobiles or Towers MUST be erected as per these procedures. Not erecting the scaffold to these
 procedures could lead to the Scaffold Erector being liable to prosecution by WorkSafe NZ for noncompliance with manufacturer's instructions.

Mobile Profiles:-


- 1.8 2m Mobile 1.2m End Frame + Guardrail Frame with One Platform use Hinged Access Deck.
- 1.95 2.15m Mobile 1.6m End Frame + Guardrail Frame with One Platform
- 2.3 2.5m Mobile 2m End Frame + Guardrail Frame with One Platform
- 2.7 2.9m Mobile 1.6m + 0.8m End Frames + Guardrail Frame with One Platform
- 3.1 3.3m Mobile 2m + 0.8m End Frames + Guardrail Frame with One Platform
- 3.5 3.9m Mobile 2m + 1.2m End Frame + Guardrail Frame with One or Two Platforms

Note: Anything higher than the 3.9m Mobile may have the topmost guardrail over 5 metres from the ground so caution MUST be taken to ensure this does not occur.

ALL SCAFFOLDS WITH THE GUARDRAILS OVER 5 METRES MUST BE ERECTED BY A CERTIFIED SCAFFOLDER.

Erection of 0.7m Mobile/Tower:

The following is the recommended placement of outriggers on a 0.700m wide Ali Scaff Mobile/Tower regardless of Height. Outrigger are depicted in red.









Lay out the required equipment for the base of the mobile in a safe area. Tower scaffold (no castors) need to be erected in the position that it is to be used.

Install baseplates/jacks/castors into ends of End Frames and stand upright. Engage brakes on castors wheels. Attach yellows in position depicted in picture from one frame to the other. Ensure that the yellows are connected to the standard and not the transom.

Install blues from bottom transom to the third transom opposite for each side. This type of ALI SCAFF has **NO** Plan Brace (Red). A Working Platform **must be positioned equal to or less than 3m** from supporting structure. Level all sides and adjust with screwjacks on Basejacks and Castors.

NOTE: No Plan Brace (Red) for the 0.7m wide ALI SCAFF therefore a hatch deck **MUST** be installed within 3 metres of the base.

Erection of 0.7m Mobile/Tower:







Recommend that scaffold erectors work within the scaffold structure and be protected from falls by progressively installing temporary platforms & guardrails as scaffold is erected and dismantled.

Outriggers should be installed as soon as possible to increase stability as depicted in figure **3** on page 2 when the scaffold is freestanding with no nearby structure for support.

Outriggers are installed at each corner of the scaffold when the scaffold is up against a wall or structure as depicted in figures **1 &2** on page 2.







Above is an example of a low-level mobile with a platform at 1.1 metre level.

NOTE: 3 x guardrails attached to the sides when a Guardrail Frame is **NOT used.**

The above scaffold displays the working platform using a Guardrail Frame and toeboards with the ladder protruding through the access deck. Outriggers are required at each corner of the scaffold as depicted in figures 1, 2 & 3.

The above picture depicts the use of 2 x 2 metre End Frames with a Guardrail on top.

The top guardrail is over 5 metres so if the Scaffold Erector is **NOT** a certified scaffolder he CAN NOT erect this mobile.

Below are examples of the placement of Outriggers onto the End Frame.







Ali Scaff 0.700m Wide Component Identification Sheet

